Estimate of the probable cost of improving the central block at old Silledars Lines at Bangalore.

Items of work	Per	Quantity
Removing the existing Arcot tiled roof including woodwork ...	Sq.	45·08
Removing the Bengal terrace ...	"	37·56
Roofing with 1st class Mangalore tiles laid on 6" square tiles with teak reepers, etc., complete.	"	82·64
Ridge tiles set in mortar ...	R. ft.	287
Removing the existing granite flooring ...	Sq.	87·82
Flooring with Cuddappa slabs 1½" thick diagonally and cement pointing, etc.	"	87·82
Whitewashing ...	"	191·12
Colourwashing ...	"	42·00
Silicate painting including scraping old paint ...	"	14·11
Wood oiling ...	"	69·37
Providing iron bars to all doors ...	R. ft.	16
Providing long bolts to all doors ...	No.	16
Providing teakwood bottom frames of doors ...	C. ft.	13·33
Burnt brick in chunam ...	Sq.	216
Chunam plastering ...	Sq.	3·60
Teakwood work wrought and put up including wood oiling ...	C. ft.	337·41
Burnt brick in chunam cornice work (9"×9") complete ...	R. ft.	358
Dismantling brick in clay wall ...	C. ft.	18,297
Removing Arcot tiles in roof including teakwood rafters and bressummers, etc., and stacking.	Sq.	57·00
Removing and stacking stone pillars 8 ft. to 14 ft. length and 1½ ft. to 1½ ft. in width ...	Each	2473

Estimate of the probable cost of improving the compound wall of old Silledars Lines at Bangalore.

Items of work	Per	Quantity
Dismantling the existing compound wall ...	C. ft.	8,525
Burnt stone in clay including bond slabs ...	"	1,960
Burnt brick in clay ...	"	4,394
Chunam plastering ...	Sq.	77·16
Burnt brick in mortar coping ...	R. ft.	620
White and colourwashing as per plastering ...	Sq.	77·16

C. VIJAYARANGAM NAIDU,
Executive Engineer.

KOLAR DIVISION.

Notice.

The attention of the public is invited to the notification published in the issue of the *Mysore Gazette* dated the 31st January 1918, pages 103—104, calling for tenders for restoring the Pulurkota tank, Registered No. 144 of Srinivaspur Taluk.

Notice.

The attention of the public is drawn to the notification published in the *Mysore Gazette*, dated the 14th February 1918, Part IV, pages 148—149, calling for tenders for constructing a separate building for the Anglo-Vernacular School at Bowringpet.

V. V. KARVE,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification.

Attention is invited to the notice calling for tenders for improving and extending A.-V. School at Kunigal, published in Part IV of the *Mysore Gazette* dated 14th February 1918, page 149.

N. G. KRISHNA IYENGAR,
Offg. Executive Engineer.

MYSORE HEADQUARTER RANGE.

Abstract Notification.

Attention is invited to the notice calling for tenders for dismantling the Band Room and constructing a new Car shed at the South Gate of Fort, Mysore, published in Part IV of *Mysore Gazette*, dated 14th February 1918, pages 150 and 151.

GURU RAO SIRSI,
Assistant Engineer.